.1 General Information

- .1 Group motor starters in mechanical or electrical rooms in a motor control centre. Obtain permission from FMGT if loose starters have to be used.
- .2 Motor control centre are to be install on a concrete housekeeping pad..

.2 Shop Drawings

- .1 Submit shop drawings that indicate:
 - .1 Outline dimensions
 - .2 Configuration of identified compartments.
 - .3 Floor anchoring method and dimensioned foundation template.
 - .4 Cable entry and exit locations.
 - .5 Dimensioned position and size of busbars and details of provision for future extension.
 - .6 Schematic and wiring diagrams.

.3 Supply Characteristics

[347/600] [120-/208] V, 60Hz, wye connected, 3 phase, 4 wire, grounded neutral.

.4 Vertical Section Construction

- .1 Independent vertical sections fabricated from rolled flat steel sheets bolted together to form rigid, completely enclosed assembly.
- .2 Each vertical section divided into compartment units, minimum 305 mm high, or as indicated.
- .3 Each unit to have complete top and bottom steel plate for isolation between units.
- .4 Horizontal wireways, equipped with cable supports, across top and bottom, extending full width of motor control centre, isolated from busbars by steel barriers.
- .5 Vertical wireways c/w doors for load and control conductors extending full height of vertical sections, and equipped with cable tie supports. Installation wiring to units accessible with doors open and units in place.
- .6 Openings, with removable coverplates, in side of vertical sections for horizontal wiring between sections.
- .7 Incoming cables to enter at [top] [bottom] with terminals.
- .8 Provision for outgoing cables to exit via top or bottom with terminals.
- .9 Removable lifting means.
- .10 Provision for future extension of both ends of motor control centre including busbars without need for further drilling, cutting or preparation in field.
- .11 Divide assembly for shipment to site, complete with hardware and instructions for re-assembly, as recommended by the manufacturer.

.5 Sills

.1 Continuous 75 mm channel iron floor sills for mounting bases with 19 mm diameter holes for bolts.

.6 Busbars

.1 Main horizontal and branch vertical, three phase and neutral high conductivity tin plated copper busbars in separate compartment [bare] self-cooled, extending entire width and

height of motor control centre, supported on insulators and rated as required using standard products.

- .2 Branch vertical busbars for distribution of power to units in vertical sections.
- .3 No other cables, wires, equipment in main and branch busbar compartments.
- .4 Brace buswork to withstand effects of symmetrical short-circuit current as required.
- .5 Bus supports: with high dielectric strength, low moisture absorption, high impact material and long creepage surface designed to discourage collection of dust.

.7 Ground Bus

- .1 Copper ground bus extending entire width of motor control centre.
- .2 Vertical ground bus strap, full height of section, tied to horizontal ground bus, engaged by plug-in unit ground stab.

.8 Motor Starters And Devices

.3 Refer to Section 26 29 10 Motor Starters to 600 V.

.9 Starter Unit Compartments

- .1 Units EEMAC size 5 and smaller, circuit breaker units 225A and smaller, plug-in type with self-disconnect. Guide rail supports for units to ensure that stabs make positive contact with vertical bus. Provision for units to be installed or removed, off load, while buses energized.
- .2 Unit mounting:
 - .1 Engaged position unit stabbed into vertical bus.
 - .2 Withdrawn position unit isolated from vertical bus but supported by structure. [Terminal block accessible for electrical testing of starter].
 - .3 Provision for positive latching in either engaged or withdrawn position and padlocking in withdrawn position.
 - .4 Stab-on connectors free floating tin plated clips, self-aligning, backed up with steel springs.
- .3 External operating handle of circuit switch interlocked with door to prevent door opening with switch in "on" position. Provision for [3] padlocks to lock operating handle in "off" position and lock door closed.
- .4 Hinge unit doors on same side.
- .5 Overload relays manually reset from front with door closed.
- .6 Pushbuttons and indicating lights mounted on door front.
- .7 Devices and components by one manufacturer to facilitate maintenance.
- .8 Pull-apart terminal blocks for power and control to allow removal of starter units without removal of field wiring.

.10 Equipment Identification

.1 Motor control centre main nameplate: size No. 7, engraved "MCC ##" on the first line, "[347/600V] [120/208V] 3 phase, 4 wire" on the second line.

Individual compartment nameplates: size No. [5], engraved as indicated.