Facilities Notice

Capital Development & Delivery | Facilities Management
Saunders Building PO Box 1700 STN CSC Victoria BC V8W 2Y2 Canada
T 250-721-7591 | www.uvic.ca/fmgt

Title:	Harry Hickman Building, HHB – Building Automation System Maintenance - UPDATE
Location:	Harry Hickman Building, Building #215 – Legacy Controller #4A8 Upgrade
Description:	Facilities Management has contracted SRD Controls to update the Building Automation System DDC Controller in the upper mechanical room #202. This controller is responsible for running the heating water system in room 120 and its exhaust fan. The building will undergo normal morning warm up if needed prior to the controller being replaced. Following the controller upgrade, all the system Inputs and Outputs (HVAC, temperature sensors, heating control valves, etc.) will be tested to ensure they operate as expected.
Time frame:	Thursday, October 6th and 7th, 2026
FMGT contact:	Peter Lagan, Building Automation System Manager
Email address:	plagan@uvic.ca
Phone:	250-880-1773