

INJECTION TEST: BUILDING A DATA INJECTOR FOR THE ATLAS LIQUID ARGON SIGNAL PROCESSOR

2022 WINTER NUCLEAR AND PARTICLE PHYSICS CONFERENCE

MAHEYER J. SHROFF
UNIVERSITY OF VICTORIA



FEB 18 2022

ATLAS AT THE LHC





FIG 1: SKETCH OF THE UNDERGROUND LHC ACCELERATOR RING WITH ITS MAIN EXPERIMENTS [1]

- The Large Hadron Collider is a $p - p$ accelerator colliding protons at $\sqrt{s} \sim 13$ TeV.
- Protons are accelerated in bunches and collide every 25ns with a maximum peak luminosity so far of $2 \times 10^{34} \text{cm}^{-2}\text{s}^{-1}$
- The ATLAS detector is a cylindrical multi-purpose detector placed at one of the interaction points around the LHC ring.
- The Large Hadron Collider is due to undergo major design changes with the goal of colliding protons at $\sqrt{s} = 14$ TeV and with a peak luminosity of up to $7.5 \times 10^{34} \text{cm}^{-2}\text{s}^{-1}$.

THE NEED FOR AN INJECTOR


FIG 3: SCHEMATIC OF THE PHASE II UPGRADE (CROPPED) [2]



- Signals from the calorimeter and the FEB2 will not be available as the LASP is developed
- Monte Carlo simulations can mimic FEB2 pulses for different physics events
- As the LASP is being developed, it needs to be tested with external test cases to verify operation.

THE NEED FOR AN INJECTOR

FIG 3: SCHEMATIC OF THE PHASE II UPGRADE (CROPPED) [2]



- As the LASP is being developed, it needs to be tested by external test cases to verify operation.
- Thus, we need a data injector that will input pulses similar to those expected from the FEB2s

REQUIREMENTS FOR THE INJECTOR

5/10

- The Injector project is an integral part of the LASP test-bench.

SPECIFICATION (SUMMARIZED)

“The data injector shall provide, with the **highest fidelity**, **22 channels** of **FEB2 payloads** transmitted at **10.24 Gbps**. The payload should be **user-controlled** which can help test the LASP for different cases. Data injection should occur for **as long as possible**”

- ➔ **Highest fidelity:** Ability to maintain transmission accuracy
- ➔ **22 channels:** 22 independent streams of data
- ➔ **FEB2 payloads:** payload structure as transmitted by FEB2s i.e. 12 ADCs + 2 BCIDs (Bunch Crossing IDs)
- ➔ **10.24 Gbps:** FEB2 transmission speed
- ➔ **User-controlled:** user having the ability to manipulate the values
- ➔ **As long as possible:** duration of injection

FPGAs

- The Injector (and the LASP) is built on a firmware programmable integrated circuit called an **FPGA** (Field Programmable Gate Array)
- FPGA devices contain logic cells and programmable switches. Logic cells can be programmed to perform functions, while the programmable switches can be customized to provide interconnections between logic cells.
- The Injector is implemented on an Intel Stratix 10 GX FPGA board




FIG 4: FRONTAL IMAGE OF THE INTEL STRATIX 10 GX BOARD [3]


The Stratix 10 board has the following capabilities which are exploited for the Injector project

- ✓ **100 Gbps transceivers**
- ✓ **1 Gbps Ethernet connector**
- ✓ **2 GB external memory device**

DESIGN SCHEME & IMPLEMENTATION

7/10

FIG 5: OVERVIEW OF INJECTOR DESIGN



Broken down into two stages:

1. Transfer data from PC into storage via Ethernet using the UDP/IP protocol
2. Retrieval of data from storage.
Packaging of data in a format that replicates the FEB2 payload

- ✓ The injector monitors incoming Ethernet frames and strips it down to provide a UDP payload only
- ✓ As a consequence, the Injector "lives" inside an Ethernet network
- ✓ Data sent from the Ethernet is then stored in a 2GB External memory device.
- ✓ Once all 2GB of data is stored, the contents are retrieved, packaged and are sent to the LASP
- ✓ Injection of contents continues until user intervention

ETHERNET DATA TRANSFER

8/10

- Using a packet sniffer (e.g. Wireshark), one can intercept and monitor the traffic across a particular network.
- The injector is tested by connecting it to a moderately busy campus network switch. The workstation sending the data is connected to the *same* network switch.
- Dumping of contents received by the injector show that all the ethernet packets are transferred correctly




FIG 6: DATA TRANSMISSION SPEED AS MONITORED BY AN ETHERNET PACKET SNIFFER

**The Ethernet throughput is measured @ ~930Mbps i.e. takes ~18s to send 2GB
This is at the limit of the GbE protocol.**

DATA INJECTION TO LASP

- Signals inside the FPGA can be probed and measured - somewhat like an oscilloscope.
- To verify the injection, the signals received by the LASP are monitored and are confirmed to be the same as sent by the injector. Additionally, a simple checksum is sent with every payload and recalculated at the receiving end to verify transmission accuracy
- The incoming signal from the injector as well as the error counter (checksum verification) is probed continuously.

Normal sequence

	⊕ \pgbtFpga_top_inst uplinkuserdata_o[229..0]	0C001600023710370F370E370D370C370B370A37093708370737063705h	X	0C000E0002371C371B371A371937183717371637153714371337123711h
	⊕ \gen_downlink_data:verify_payload xor_result[31..0]		0000000h	
	⊕ \gen_downlink_data:verify_payload error_count[55..0]		00000000000000h	

Transmission accuracy = 100%*

* The checksum will not be able to detect a flipping of an even number of bits.
The FEB2-LASP protocol used has advanced correction features (e.g FEC) which ensures the integrity of data transmission

CONCLUSIONS

- The Injector project is designed and built and is now being used within the LASP firmware community.

SPECIFICATION (SUMMARIZED)

“The data injector shall provide, with the **highest fidelity**, **22 channels** of **FEB2 payloads** transmitted at **10.24 Gbps**. The payload should be **user-controlled** which can help test the LASP for different cases. Data injection should occur for **as long as possible**”

- ➔ **Highest fidelity**: 100% transmission accuracy
- ➔ **22 channels**: Only 4 channels implemented (limited by FPGA hardware)
- ➔ **FEB2 payloads**: 12 ADCs + 2BCIDs are extracted from the memory device ...
- ➔ **10.24 Gbps**: ... and are transmitted at the FEB2 speeds ...
- ➔ **User-controlled**: 2 GB of user-defined data
- ➔ **As long as possible**: for an indefinite period

THANK YOU!

YOUR QUESTIONS/COMMENTS ARE MOST APPRECIATED

SPECIAL MENTION 🙌🙏

This work has been made possible by the very gracious help and support of the following people

- My supervisors - Prof. R. Keeler and Prof. R. McPherson
- Dr. Sam de Jong and the whole LASP Firmware group

REFERENCES

REFERENCES

- (1) LHC Underground layout with its experiments, <http://te-epc-lpc.web.cern.ch/te-epc-lpc/machines/lhc/pagesources/LHC-Underground-Layout.png>. Accessed: Jan 2022
- (2) The ATLAS Collaboration. ATLAS Liquid Argon Calorimeter Phase-II Upgrade Technical Design Report, 2018
- (3) Intel Corp. Intel Stratix 10 GX FPGA Development Kit User Guide, 2019